

RA3090

(13)

(1)

Casting - Fred + Pat Biggs
Includes sales tax on all materials

7-1-97

Foundation (see attached)

All excavation + backfill, electric + water
lines installed. Form block fdn, waterproofing,
drainage tile, above grade garage, below floor
plumbing, driveway base, septic system \$ 17,490

concrete floors 2,450
floor insulation + heat tube 2,735

Framing

Material (dimension lumber + plywoods) \$ 13,415

trusses 1,840

TJI's 4,137

\$ 19,392

Framing labor inc: all interior walls (3 floors)
install doors (ext) + windows, sheathing, sub-fascia,
openings, pocket door hardware (complete, ready for install) \$ 7,468

Roofing 24 sq @ \$92 labor + mat 2,208

Windows + Doors (see attached)

